Proposal PR2504-0617

Ref. customer : Villa 293 Low Voltage
Date of proposal : 29/04/2025
Validity ending date : 06/05/2025
Customer Code : CU2502-00377

From

Smart Tech for Security Devices and Sys Installation and Maintenance Co
Block 6, Khaled Ibn Alwaleed St
Building 6, Floor 10
15300 Sharq

Phone: +965 91102236 - Fax: +965 25317620
Email: support@smarttech.com.kw
Web: https://smarttech.com.kw

To

Alshaikha Alia Salem Al-Ali Al-sabah
Qortuba B1_H293

Amount in Kuwaiti Dinar currency

Description		Unit Price	Qty	Disc.	Total
UNV-0006 - NVR301-04-P4 4-channel input Plug & Play with 4 independent PoE network interfaces Third-party IP cameras supported with ONVIF conformance Support 1-ch HDMI, 1-ch VGA, and HDMI at up to 4K(3840x2160) resolution Up to 8 Megapixels resolution recording Support H.265/H.264 video formats Accurate retrieval, instant playback 1 SATA HDD up to 6 TB Support for P2P, UPnP, NTP, DHCP, PPPoE Support for mobile client access		35.000	2	15%	59.500
UNV-0002 - IPC2124LB-SF40KM-G Bullet 4MP Mini Fixed Bullet Network Camera 4.0mm@F2.0 High quality image with 4MP, 1/3"CMOS sensor 4MP (2560*1440)@25/20fps; 3MP (2304*1296)@30/25fps; 2MP (1920*1080)@30/25fps; 720P (1280*720)@30/25fps Ultra 265, H.265, H.264, MJPEG Smart IR, up to 30m (98ft) IR distance Supports 128 G Micro SD card Support PoE power supply 3-Axis		23.000	6	15%	117.300
HDD_6TB_WD60PURZ - Western Digital 6TB WD Purple WD60PURZ Western Digital 6TB WD Purple Surveillance Internal Hard Drive HDD - SATA 6 Gb/s, 64 MB Cache, 3.5" - WD60PURZ		75.000	2	15%	127.500

Proposal PR2504-0617

Ref. customer : Villa 293 Low Voltage
Date of proposal : 29/04/2025
Validity ending date : 06/05/2025
Customer Code : CU2502-00377

ST-0006 - Cabinet 9U 60x45 Cabinet 9U (600*450mm) wall mount rack with glass door.		40.000	2	15%	68.000
AKU-0005 - Akuvox R20A on-wall SIP Intercom with one Button (Video & Card reader) Body material: Zinc alloy Camera: 3M pixels, automatic lighting,Wide-angle camera: 120 RF Card Reader 13.56MHZ&125KHZ Card reader Output Relay: 2 output relays for door opener Water-proof & Dust-proof: IP65 Installation: Surface Mount model or Flush Mount model PoE (IEEE802.3af, Power-over-Ethernet); Two-way audio communication over IP networks with Echo Cancel Complies with SIP standard for easy integration in every SIP PBX;		80.000	2	15%	136.000
AKU-0022 - R20A in-wall Bracket		16.000	2	15%	27.200
AKU-0016 - Akuvox S563 8-inch S563 8-Inch SIP Premium Indoor Monitor The Akuvox S563 is an 8-inch SIP indoor monitor that runs on the Android 12 operating system. It features an exceptional speaker and a high-resolution touchscreen display, ensuring an unparalleled audio-visual intercom experience.		80.000	6	15%	408.000
GS-0017 - GWN7661E Wi-Fi 6 In-Wall AP GWN In-Wall Wi-Fi 6 Access Point • 3 Gbps wireless throughput and 4x Gigabit wireline ports • 2x2:2 (2.4G) and 3x3:2 (5G) MU-MIMO and OFDMA technology • Supports up to 256 concurrent Wi-Fi client devices • Self-power adaptation upon auto-detection of PoE or PoE+ • Advanced QoS to ensure real-time performance of low-latency applications • Anti-hacking secure boot and critical data/control lockdown via digital signatures, unique security certificate/random default password per device • Embedded controller manages up to 50 local GWN APs; GDMS Networking offers unlimited AP management, & GWN Manager offers on-premise software AP management		44.000	18	15%	673.200

Proposal PR2504-0617

Ref. customer : Villa 293 Low Voltage
Date of proposal : 29/04/2025
Validity ending date : 06/05/2025
Customer Code : CU2502-00377

GS-0027 - GWN7803P 24 ports POE Grandstream USA. Layer2+ Managed Switch, 24xPoE Gig, 4 SFP Gig, 30W/Port, 360W Total		138.000	2	15%	234.600
ST-0085 - SK-KIT16 Satellite SK Plus Satellite Kit Enhance your TV setup with the SK Plus Satellite Kit. This kit includes: 2 high-quality 3-foot satellite dishes, made in Turkey 2 sturdy mounting brackets 2 LNBs for better signal reception 1 16-channel switch for connecting multiple channels		168.000	2	15%	285.600
ST-0035 - System Installation Installation, basic configuration, and commissioning - One-year warranty for the camera system claimed from the vendor. - One-year warranty for the Satellite system claimed from the vendor. - One-years warranty for the Intercom system claimed from the vendor. - One-year warranty for the Wifi system claimed from the vendor. - Civil, Electrical, Cabling, Conduit & Conduiting work are not included in this offer.		250.000	1		250.000

Payment Terms: As per the contract terms

Payment method: Online payment

Total net before discount	2,764.000
Total discount	377.100
Total	2,386.900

Written acceptance, company stamp, date and signature